



ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	CLSP-1	2	1/4" PLATE		HDG	0.65
2	27-4201-005	16	3/8" x 1 1/4" GR.5 HDG BOLT			0.06
3	27-5010-005	4	3/8 A36 HDG FLAT WASHER			0.01
4	27-5020-005	16	3/8" HDG LOCK WASHER			0.01
5	27-5030-005	16	3/8" HDG HEX NUT			0.02

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

STANDARD TOLERANCES:

(UNLESS OTHERWISE NOTED)

FRACTIONS ±1/16"
 DECIMALS ±0.01"
 ANGLES ±0.5°


NEWAVE
 TOWER COMPONENTS. 503-792-3739
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 2.7 LB

QTY:

FINISH: HDG

JOB #:

TITLE: CABLE LADDER HARDWARE KIT			DRAWN BY: KY	DATE: 5/23/2024	CHK'D BY: KY
SERIES: COAX SUPPORT			DRAWING NO. CLHK		
SHEET: 1 OF 1					