



DETAIL - A

STANDARD TOLERANCES:

(UNLESS OTHERWISE NOTED)
FRACTIONS ±1/16"
DECIMALS ±0.01"
ANGLES ±0.5°

NEW VE
TOWER COMPONENTS. 503-792-3739
10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 250.25 LB QTY:

FINISH: JOB #:

ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	WB5015-10	1	7" x 2" x 14 GA GRIP STRUT	10'	G90 HDG	30.76
2	P35-160	2	3" STD PIPE	13'-4"	HDG	101.12
3	HB12.01	2	WAVEGUIDE BRIDE SUPPORT 12" (HORSE HEAD)		HDG	5.87
4	PC35	2	3-1/2" O.D PIPE CAP		HDG	0.30
5	27-4210-005	6	3/8" x 2 3/4" GR.5 HDG FULLY THREADED BOLT			0.10
6	27-5010-005	6	3/8" A36 HDG FLAT WASHER			0.01
7	27-5020-005	6	3/8" HDG LOCK WASHER			0.01
8	27-5030-005	6	3/8" HDG HEX NUT			0.02
9	SFW-716G	6	1/4" x 1 5/8" SQ. WASHER WITH 7/16" DIA HOLE		HDG	0.18
10	27-6090-005	4	GALV. 1/2" x 3 5/8" x 5" U-BOLT ASSEMBLY			0.74
TITLE:				DDAMN BY: DATE:		CHKID BY:

SHEET: 1 OF 1

WAVEGUIDE BRIDGE KIT, 11-3/4" WIDE (2) BURIAL POSTS W/ 13'-4" COLUMNS

SERIES: COAX ICE BRIDGE

DRAWING NO.
WB5000-7DB

5/14/2019