



ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	WB5011-10	1	24" x 2" x 14 GA GRIP STRUT	10'	HDG	74.00
2	HB24	2	24" WIDE WAVEGUIDE BRIDGE WELDMENT			14.47
3	P35-160	2	3" STD PIPE @ 13'-4" LONG			101.12
4	PC35	2	3-1/2" O.D PIPE CAP		HDG	0.30
5	BSM35	1	BASE SHOE MOUNT			21.20

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

**STANDARD TOLERANCES:**  
 (UNLESS OTHERWISE NOTED)  
 FRACTIONS ±1/16"  
 DECIMALS ±0.01"  
 ANGLES ±0.5°

**NEWAVE**  
 TOWER COMPONENTS. 503-792-3739  
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 327 LB  
 QTY:  
 FINISH:  
 JOB #:

TITLE:	WAVEGUIDE BRIDGE KIT (1) BURIAL POST W/ (A) 13'-4" COLUMNS		DRAWN BY: JG	DATE: 7/17/2018	CHK'D BY:
SERIES: COAX ICE BRIDGE	SHEET: 1 OF 1		DRAWING NO. WB5000-U-24		