



THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

STANDARD TOLERANCES:
 (UNLESS OTHERWISE NOTED)
 FRACTIONS ±1/16"
 DECIMALS ±0.01"
 ANGLES ±0.5°

NEWAVE
 TOWER COMPONENTS. 503-792-3739
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 285.75 LB

QTY:

FINISH: HDG

JOB #:

ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	WB5011-12	1	24" x 12' x 2" DEEP GRIP STRUT BRIDGE CHANNEL		HDG	53.96
2	HB24	2	24" WIDE WAVEGUIDE BRIDGE WELDMENT			14.47
3	P35-160	2	3" STD PIPE @ 13'-4" LONG			101.12
4	PC35	2	3-1/2" O.D PIPE CAP		HDG	0.30

TITLE: WAVEGUIDE BRIDGE KIT (2) BURIAL POSTS W/ 13'-4" COLUMNS			DRAWN BY: JG	DATE: 7/17/2018	CHK'D BY:
SERIES: COAX ICE BRIDGE			DRAWING NO. WB5001-24DB12		
SHEET: 1 OF 1					