



ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	WP-SCAM-24-2.01	1	T-ARM WELDMENT		HDG	56.21
2	WP-SCAM-24-2.06	1	C3x3.5	1'-4"	HDG	5.46
3	TR58-18	2	5/8" x 18" A36 HDG ALL-THREAD	1'-6"		1.56
4	27-5380-005	4	5/8 HDG LOCK WASHER			0.03
5	27-5391-005	4	5/8" HDG HEX NUT			0.08

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

**STANDARD TOLERANCES:**

(UNLESS OTHERWISE NOTED)

FRACTIONS ±1/16"  
 DECIMALS ±0.01"  
 ANGLES ±0.5°

**NEWAVE**  
  
 TOWER COMPONENTS. 503-792-3739  
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 65.25 LB

QTY:

FINISH:

JOB #:

TITLE:

WOODPOLE MOUNT, 22" STANDOFF  
 SMALL CELL ANTENNA MOUNT

SERIES: WOODPOLE MOUNTING

SHEET: 1 OF 1

DRAWN BY:

JG

DATE:

6/24/2019

CHK'D BY:

KY

DRAWING NO.

WP-SCAM-24-2