



ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	AM1030-23M.02	1	STIFF ARM HALF CLAMP WELDMENT		HDG	0.92
2	AM1030-23M.03	1	1/4" PLATE		SEE W/O	0.58
3	AM1031.03	1	1/4" PLATE		HDG	1.79
4	AM1031HD.03	2	3/16" PLATE		HDG	1.58
5	TR12-10	2	GALV. 1/2" x 10" ALL-THREAD			0.56
6	27-4310-005	2	GALV. 1/2" x 4" GR.5 FULL THREADED BOLT			0.27
7	27-4300-005	2	1/2" x 1 1/4" GR.5 HDG BOLT			0.12
8	27-5200-005	8	HDG - 1/2" FLAT WASHER, USS			0.04
9	27-5210-005	8	1/2 HDG LOCK WASHER			0.01
10	27-5222-005	8	1/2 HDG HEX NUT			0.04

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

STANDARD TOLERANCES:
 (UNLESS OTHERWISE NOTED)
 FRACTIONS ±1/16"
 DECIMALS ±0.01"
 ANGLES ±0.5°

NEWAVE
 TOWER COMPONENTS. 503-792-3739
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 9.1 LB
 QTY:
 FINISH:
 JOB #:

TITLE:	STIFF ARM MOUNT UNIVERSAL KIT		DRAWN BY: JG	DATE: 7/17/2018	CHK'D BY: KY
SERIES: TOWER ANTENNA MOUNT	SHEET: 1 OF 1		DRAWING NO. AM1030-UC5		