


DETAIL - A

ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	MF1236-3.01	3	UNIVERSAL 12" TO 36" RING MOUNT WELDMENT		HDG	50.60
2	AM1014-XP.01	3	CROSS OVER CHANNEL WELDMENT		HDG	23.82
3	AM1014-XP-SQ.01	3	3/8" PLATE		HDG	10.84
4	M3015-12.01	3	SINGLE SUPPORT ARM 12" STAND OFF WELDMENT		HDG	29.58
5	ST35-316-72	3	HSS 3 1/2x3 1/2x3/16"	6'	HDG	48.88
6	27-5580-005	9	3/4" x 28" B7 HDG ALL-THREAD	2'-4"		3.51
7	27-5481-005	18	3/4 A36 HDG FLAT WASHER			0.11
8	27-5490-005	18	3/4" HDG LOCK WASHER			0.04
9	27-5500-005	18	3/4" HDG HEAVY HEX NUT			0.21
10	27-5440-005	12	5/8" x 2 1/4" A325 HDG BOLT			0.30
11	27-5370-005	12	5/8 A36 HDG FLAT WASHER			0.08
12	27-5380-005	12	5/8" HDG LOCK WASHER			0.03
13	27-5390-005	12	5/8 HDG HEAVY HEX NUT			0.13
14	27-5300-005	24	1/2 x 5 A325 HDG BOLT			0.34
15	27-5220-005	24	1/2" HDG HEAVY HEX NUT			0.07
16	27-5210-005	24	1/2" HDG LOCK WASHER			0.01
17	27-6235-005	6	HDG - 5/8" x 4-5/8" x 7-1/2" U-BOLT ASSEMBLY		HDG	1.99

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

STANDARD TOLERANCES: (UNLESS OTHERWISE NOTED) FRACTIONS ±1/16" DECIMALS ±0.01" ANGLES ±0.5°	 NEWAVE TOWER COMPONENTS, 503-792-3739 10910 PORTLAND RD. BROOKS, OR 97305	TOTAL WT: 600.35 LB QTY: FINISH: HDG JOB #:
--	---	--

TITLE: 3-SEC MONOPOLE T-ARM FRAME, 12" STAND-OFF 3-1/2" SQ TUBE FACE X 6'-0" LONG		DRAWN BY: RJ DATE: 4/19/2024	CHK'D BY: KY
SERIES: MONOPOLE MOUNTING	SHEET: 1 OF 2	MTTF3-126	