



ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	AMCS-3.01	8	1/2" PLATE		SEE W/O	1.26
2	TR12-12	4	1/2" x 12" A36 HDG ALL-THREAD	1'		0.67
3	27-5200-005	16	1/2" A36 HDG FLAT WASHER			0.04
4	27-5210-005	16	1/2" HDG LOCK WASHER			0.01
5	27-5222-005	16	1/2" HDG HEX NUT			0.04

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

**STANDARD TOLERANCES:**

(UNLESS OTHERWISE NOTED)

FRACTIONS - 1/16"  
 DECIMALS - 0.01"  
 ANGLES - 0.5°



TOWER COMPONENTS. 503-792-3739  
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 14.25 LB

QTY:

FINISH:

JOB #:

TITLE:

PIPE-TO-PIPE CLAMP KIT  
 FOR 1-1/2" TO 3-1/2" OD PIPE

DRAWN BY:

JG

DATE:

6/5/2019

CHK'D BY:

KY

DRAWING NO.

AM1019-3

SERIES: TOWER ANTENNA MOUNTING

SHEET: 1 OF 1