



TOP VIEW

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

STANDARD TOLERANCES:

(UNLESS OTHERWISE NOTED)
 FRACTIONS - 1/16"
 DECIMALS - 0.01"
 ANGLES - 0.5°

NEWAVE
 TOWER COMPONENTS. 503-792-3739
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 20.3 LB

QTY:

FINISH:

JOB #:

ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT	
1	MRRU-4.01	2	RRU CLAMP WELDMENT FOR 4" SQ. STAND OFF		HDG	9.13	
2	27-4320-005	4	GALV. 1/2" x 7" GR.5 FULL THREADED BOLT			0.44	
3	27-5210-005	4	1/2 HDG LOCK WASHER			0.01	
4	27-5222-005	4	1/2 HDG HEX NUT			0.04	
TITLE:			RRU CLAMP KIT, ATTACHES TO 4" SQ STAND-OFF TUBE		DRAWN BY: JG	DATE: 7/17/2018	CHK'D BY: KY
SERIES: MONOPOLE MOUNTING			SHEET: 1 OF 1		DRAWING NO. MRRU-4		