



TOP VIEW

ITEM	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT WT
1	RT-RRU4.01	2	L2 1/2x2 1/2x3/16"	3'-4"		10.24
2	RT-RRU5.01	2	ROOFTOP NON-PENETRATING TRAY WELDMNT		HDG	38.62
3	RT-RRU5.07	4	3/8" PLATE		HDG	8.35
4	RT-RRU5.08	2	1 5/8" P1000T @ 10' LONG (CUT IN HALF)	5'		8.12
5	AMCS-3.01	4	1/2" PLATE		SEE W/O	1.26
6	AMCS-5.01	4	1/2" PLATE		SEE W/O	2.25
7	CXP1	2	3/8" PLATE		SEE W/O	4.81
8	P23-48	2	2" STD PIPE	4'	HDG	14.63
9	TR12-6	8	1/2" x 6" HDG ALL-THREAD	6"		0.33
10	27-4307-005	4	1/2" x 3" GR.5 HDG BOLT			0.22
11	27-4303-005	8	1/2" x 2" GR.5 HDG BOLT			0.16
12	27-5200-005	28	1/2 A36 HDG FLAT WASHER			0.04
13	27-5210-005	28	1/2 HDG LOCK WASHER			0.01
14	27-5222-005	28	1/2 HDG HEX NUT			0.04
15	27-6060-005	4	GALV. 1/2" x 2-1/2" x 4" GR-5 U-BOLT ASSEMBLY			0.76

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

STANDARD TOLERANCES:

(UNLESS OTHERWISE NOTED)
 FRACTIONS - 1/16"
 DECIMALS - 0.01"
 ANGLES - 0.5°



TOWER COMPONENTS. 503-792-3739
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 210.8 LB

QTY:

FINISH:

JOB #:

TITLE:

ROOFTOP RRU MOUNT
 40"W x 60"L x 48"T

SERIES: ROOFTOP MOUNTING

SHEET: 1 OF 1

DRAWN BY:

KY

DATE:

2/18/2021

DRAWING NO.

RT-RRU4-S

CHK'D BY:

-