



ITE	PART #	QTY	DESCRIPTION	LENGTH	FINISH	UNIT W
1	WB5011-10	2	24" x 2" x 14 GA GRIP STRUT	10'	HDG	74.00
2	BSP104H	4	4-HOLE BASE SHOE POST x 10'-6"		HDG	88.08
3	WB5020-48.01	2	WAVEGUIDE BRIDGE		HDG	23.51
4	PC35	4	3-1/2" O.D PIPE CAP		HDG	0.30
5	27-4210-005	16	GALV. 3/8" x 2-3/4" GR.5 FULL THREADED BOLT			0.10
6	27-5010-005	16	GALV. 3/8" FLAT WASHER		HDG	0.02
7	27-5020-005	16	3/8" HDG LOCK WASHER			0.01
8	27-5030-005	16	3/8" HDG HEX NUT			0.02
9	SFW-716G	16	GALV. 1-1/2" SQUARE WASHER W/ 7/16" HOLE		HDG	0.08
10	27-6090-005	4	GALV. 1/2" x 3 5/8" x 5" U-BOLT ASSEMBLY			0.91

THIS DESIGN AND INFORMATION CONTAINED ON THIS PRINT IS THE PROPERTY OF VALLEY FAB CORPORATION. ANY REPRODUCTION, DUPLICATION OR TRANSFER OF THE PROPRIETARY CONTENT IS PROHIBITED WITHOUT WRITTEN PERMISSION.

STANDARD TOLERANCES:

(UNLESS OTHERWISE NOTED)
 FRACTIONS - 1/16"
 DECIMALS - 0.01"
 ANGLES - 0.5°

NEWAVE
 TOWER COMPONENTS. 503-792-3739
 10910 PORTLAND RD. BROOKS, OR 97305

TOTAL WT: 555.8 LB

QTY:

FINISH: HDG

JOB #:

TITLE:		WAVEGUIDE BRIDGE KIT		DRAWN BY:	DATE:	CHK'D BY:
		(4) BASE SHOE POSTS W / 10'-6" COLUMNS		JG	7/17/2018	
SERIES: COAX ICE BRIDGE		SHEET: 1 OF 1		DRAWING NO. WB5002-48BSP		